


F00434 SK7



6-3	44 28 50	103.295(New)
	44 28 46	103.274(Po)
	4	0.021

Penilik: Foo434 SK7 Tarikh: 23/03/2024
 Stn. 2 Koordinat: S16788 B57.564 Selangor
 T.R. 1 B.K. Ms.
 Tiodolit Satu bah. aras ufuk:

Waktu	Sasaran	Ufuk	Gelembong	Puguk		
	T.R.	70 00 00				
17 19	M.H.	292 23 12		60 08 47	Waktu purata	17 19 30
17 19	M.H.	291 46 30		60 17 17	Beza dari U.T. -	8 00 00
17 20	M.H.	111 46 46		299 36 18	U.T.	9 19 30
17 20	M.H.	112 24 10		299 29 40	Deklinasi	1 17 09
	T.R.	250 00 00				
	T.R.	70 00 00				
17 21	M.H.	292 24 51		60 41 52	Waktu purata	17 21 30
17 21	M.H.	291 48 19		60 47 48	Beza dari U.T. -	8 00 00
17 22	M.H.	111 48 48		299 03 40	U.T.	9 21 30
17 22	M.H.	112 25 53		298 55 51	Deklinasi	1 17 11
	T.R.	250 00 00				

	Set 1	Set 2
Sudut pugak	29 39 59	29 07 28
Pembetulan	- 0 01 24	- 0 01 26
Altitud	29 38 35	29 06 02
Jarak kutub	88 42 51	88 42 49
Latitud	3 01 20	3 01 20
Azimut M.H. yang dikira	269 45 36	269 47 25
Purata ke M.H.	292 05 10	292 06 58
Selisih:	- 22 19 34	- 22 19 33
Purata ke T.R.	70 00 00	70 00 00
Azimuth T.R. sebenar	47 40 26	47 40 27
Pembetulan aras	+ 0 00 00	+ 0 00 00
Tirusan	- 0 00 37	- 0 00 37
Bering grid T.R.	47 39 49	47 39 50
Purata bering grid T.R.	47 39 50	