


No. Fail JRJ 80673

Rajah di muka

[illegible]

[illegible]

DAERAH PETALING.
MUKIM SUNGAI BUKIT
760
TANPA STAKA



7-1 168 75 75 91.906 ✓
168 76 71 91.890 20

-58' 70.016

1-7 192 2633	27.538 ✓
192 2630	27.539 PO
+237	-0.001

Penilik: JRS80673 Damansara Sutera Tarikh: 25/02/2009
 Stn. 3003 Koordinat: S11735 T1543 Selangor
 T.R. 3001 B.K. Ms.
 Tiodolit Satu bah. aras ufuk:

Waktu	Sasaran	Ufuk	Gelembong	Puguk
	T.R.	0 0 11		
9 37	M.H.	102 59 23	58 32 55	Waktu purata 9 37 30
9 37	M.H.	102 22 24	58 28 27	Beza dari U.T. - 8 00 00
9 38	M.H.	282 22 49	301 37 49	U.T. 1 37 30
9 38	M.H.	283 02 02	301 45 48	Deklinasi - 9 05 43
	T.R.	180 00 11		

	T.R.	0 0 11		
9 34	M.H.	102 51 00	59 16 00	Waktu purata 9 34 30
9 34	M.H.	102 14 28	59 10 50	Beza dari U.T. - 8 00 00
9 35	M.H.	282 15 15	300 57 04	U.T. 1 34 30
9 35	M.H.	282 54 07	301 02 32	Deklinasi - 9 05 46
	T.R.	180 00 11		

	Set 1	Set 2
Sudut pugak	31 35 34	30 53 12
Pembetulan	- 0 01 18	- 0 01 20
Altitud	31 34 16	30 51 52
Jarak kutub	99 05 43	99 05 46
Latitud	3 04 05	3 04 05
Azimut M.H. yang dikira	102 38 06	102 30 07
Purata ke M.H.	102 41 40	102 33 43
Selisih:	- 0 03 34	- 0 03 36
Purata ke T.R.	0 00 11	0 00 11
Azimuth T.R. sebenar	- 0 03 23	- 0 03 25
Pembetulan aras	+ 0 00 00	+ 0 00 00
Tirusan	- 0 00 40	- 0 00 40
Bering grid T.R.	- 0 04 03	- 0 04 05
Purata bering grid T.R.	- 0 04 04	

359° 55' 58"

M- 4' 15"