

SEL359 Kenning Utama Giant.

7/11/08

Detam Sanpads
PA 106177

3321818

2

3321818

1

4

36.386

36.386

pt.B

pt.L

1 3321818 / 521818 3309202 2 3309202 3 4

93.376

93.376

2

3 3309202 / 509202

pt.L

1 Sepans Di Axi 3053990 2 3053990 4 4

26.676

26.676

2

4 3053990 / 252990

pt.L

1 Sepans Di Axi 179931 2 179931 5 4

109.192

109.192

2

5 179931 / 359931

pt.B (sp 1009)

2 359931 / 179931 2069298 5 2069298 6 4

111.662

111.662

5

6 2069298 269298

Aj At.

pt.B (sp 1009)

Aj M4

5 269298 2069298 2192906 6 2192906 7 4

120.967

120.967

6

7 2192906 392906

pt.B (sp 1178)

6 392926 2192906 2521150 7 2521150 8 4

125.120


125.120

7

8 2521150 721150


pt.B

7 72 1150 252 1150 2719257 8 2719257 9 4 116.531 116.531
8
9 2719257 919257
pk-B (cp 1959)



1-3	179 7020	57.01200
	189 7036	57.019 N
	718	70.002

3-4	339 5757	70.122 N
	339 5750	70.12300
	77	70.001



CERAPAN MATAHARI BAGI AZIMUT

Penilik: SEL354 Kemuning Utama Tarikh: 08/11/2008

Stn. 1001 Koordinat: S17060 B18174 Selangor

T.R. 1004 B.K. Ms.

Tiodolit Satu bah. aras ufuk:

Waktu	Sasaran	Ufuk	Gelembong	Puguk
	T.R.	210 00 00		
8 11	M.H.	111 48 59	73 52 52	Waktu purata 8 11 30
8 11	M.H.	111 16 05	73 47 12	Beza dari U.T. - 8 00 00
8 12	M.H.	291 17 10	286 22 09	U.T. 0 11 30
8 12	M.H.	291 51 46	286 26 52	Deklinasi - 16 36 59
	T.R.	29 59 50		
	T.R.	210 00 00		
8 13	M.H.	111 53 07	73 25 42	Waktu purata 8 13 30
8 13	M.H.	111 20 14	73 19 56	Beza dari U.T. - 8 00 00
8 14	M.H.	291 21 13	286 47 59	U.T. 0 13 30
8 14	M.H.	291 55 58	286 54 23	Deklinasi - 16 37 01
	T.R.	29 59 50		

	Set 1	Set 2
Sudut pugak	16 17 14	16 44 11
Pembetulan	- 0 02 51	- 0 02 46
Altitud	16 14 23	16 41 25
Jarak kutub	106 36 59	106 37 01
Latitud	3 01 11	3 01 11
Azimut M.H. yang dikira	108 16 41	108 20 51
Purata ke M.H.	111 33 30	111 37 38
Selisih:	- 3 16 49	- 3 16 47
Purata ke T.R.	209 59 55	209 59 55
Azimuth T.R. sebenar	206 43 06	206 43 08
Pembetulan aras	+ 0 00 00	+ 0 00 00
Tirusan	- 0 00 06	- 0 00 06
Bering grid T.R.	206 43 00	206 43 02

Purata bering grid T.R. 206 43 01

Tarikh 2008 25/8

Dibuat untuk 38

Daripada Kemuning Utama

Ke

Pandangan Belakang	Pandangan Antara	Pandangan Hadapan	Naik	Turun	Aras Yang Dilaras	Jarak	Catitan
0.882	(2.89)				6.151	78M F1/179 (78M F1)	nail on top of culvert.
0.926	(3.08)	1.923	(6.34)				petraus jln 4th kemuning.
1.401	(4.60)	1.635	(5.33)				
3.209 -		0.968	(3.17)		7.839	78M F1/180	(nail on top of monsoon drain).
0.968		4.526			7.839	78M F1/180	di kedai baru 2 tingkat. jln R.33A
1.450	(4.76)	1.393	(4.91)				
1.386	(4.98)	1.385	(4.58)				
2.896	(9.38)	1.483	(8.78)				901001
1.407	(4.62)	1.398	(4.58)				901009
1.407	(4.62)	1.410	(4.63)				901178
2.006	(6.58)	1.144	(3.15)				901289
1.870	(6.19)	1.695	(5.56)				901458
1.551	(5.09)	1.612	(5.29)				901659
1.702		1.702	(5.59)		6.573	901659	
1.811		1.812					

Tarikh Aras

Dibuat untuk

Daripada

Ke

Pandangan Belakang	Pandangan Antara	Pandangan Hadapan	Naik	Turun	Aras Yang Dilaras
1.518 (9.98)					6.573
1.601 (5.25)	1.989	(9.87)			6.607
1.747 (9.75)	1.809	(5.92)			6.709
	1.762 (9.80)				6.889
1.293 (9.08)	1.383	(9.59)			6.968
1.573 (5.16)	1.662 (5.95)				6.099
	1.676 (5.30)				6.006
	1.566 (5.19)				6.056
7.882	7.899				

Jarak	Catitan
CP 1659	
CP 1959	
CP 1289	
TBM 1/1981 nail on top of sump	
CP 1178	
CP 1004	
TBM 1/1982 nail on top of 8th culvert	
CP 1001	

Bm 8 0653