


SFC 255 Ajabat Haining DT.

No. Fail

Rajah di muka

[illegible]

[illegible]


[illegible]

10
DA 26288

No. Fail

Rajah di muka

Stesen	BEARING / SUDUT			Dari Stn.	GARISAN		Ke Stn.	Sudut Pukak (±)	Jarak	Suhu	Jarak Antara Tupang	Jarak Mukamat
	Penyilang Kiri	Penyilang Kanan	Purata		Bearing Mukamat							



CERAPAN MATAHARI BAGI AZIMUT

Penilik Koo Chee Yong HarL Sabtu Tarikh 25/11/66 Bulan Nov Tahun 1966

Stesen T.R. B.K. Ms. Tiodolait (jenis) I Bah. Aras Ufuk - a 1

Formula:

$$\text{Kosain AZIMUT} = \frac{\text{Kos } P - \text{Sain } \phi \text{ Sain } \alpha}{\text{Kos } \phi \text{ Kos } \alpha}$$

SEL 285 / SEL 255 AKNS / Ajohet Haiwan

$$\text{Pembetulan Aras} = \frac{3}{8} (\pm R - \pm L) \text{ tenjen } \alpha$$

Waktu		Ufuk			Gelem-bong		Pugak			Tilkan ①	Bila waktu jam tangan tidak dalam lingkungan 3 menit daripada waktu piawai Hitung waktu umum.			W.U. - 12 ^J + W.T.K. - G. Bujur - E			
J	m	P.Ki	T.R.		Ki	Ka								12 ^J	00 ^m		
				25	02	13											
		⊕		118	12	49		50	50	19							
		⊕		117	37	07		50	46	22							
		P.Ka	⊕	297	39	17		299	21	42							
		⊕		298	18	57		299	28	08							
Purata ①		T.R.															
J	m																
9 ¹⁹								29	18	17							
		Purata Ke matahari		117	57	01		1	26								
		Purata Ke TR						29	16	51							
J	m	P.Ki	T.R.														
		⊕		118	21	15		50	25	35							
		⊕		117	45	10		50	22	12							
		P.Ka	⊕	297	48	08		299	47	52							
		⊕		298	26	57		299	52	27							
Purata ②		T.R.															
J	m																
								29	43	08							
		Purata Ke matahari		118	05	22		1	25								
		Purata Ke TR						29	41	43							
Kordinat Origin U/S		55061			m		Kordinat Origin T/B		21759			m		Purata Bg. Gerid T.R.		22 55 36	
Stesen U/S		2972			m		Stesen T/B		5801			m		Ditilik oleh		25/11/66. <u>AKNS</u>	
Jumlah/Sel.		U/S 63933			m		Jumlah/Sel.		T/B 19958			m		Dihitung oleh			
Jumlah/Sel. x 0.03256 ±		-0 39 42					Sel. G. Bujur = $\frac{\text{Jum.}}{\text{Sel.}} \times 0.03246 \pm$		8°05'					Tarikh			
G. Lintang Origin U		3 40 49					Sel. G. Bujur x Sain G. Lintang -										
G. Lintang Stesen U		3 06 07					T (-) / B (+) Tirusan -		26'								

P.Ki. — Penyilang Kiri
P.Ka. — Penyilang Kanan

T.R. — Tanda Rujuk

W.U. — Waktu Umum

PKNS PJ

Tarikh

Aras

Dibuat untuk

37

05/02/05

Daripada

Ke

Pandangan Belakang	Pandangan Antara	Pandangan Hadapan	Naik	Turun	Aras Yang Dilaras	Jarak	Catitan
0.968 (13.18)	0.872 (22.86)				35.529 AS		SW AS 1806 PJ 19
0.732 (22.90)	2.095 (16.88)				35.625 TBM F10/19		78M F10/19 on top of PKNS wall fence.
0.956 (13.19)					38.902 P		P
2.023 (16.69)					38.178 P		P
					33.111 TBM43		TBM 43
1.057 (13.97)	2.518 (18.26)				32.616 P		P
0.514 (2.01)	2.123 (16.97)				31.550 P2		P2
0.587 (14.91)					30.113 P0		F10
2.610 (8.58)	2.051 (16.73)				32.356 P		
2.770 (19.09)	0.367 (1.20)				39.992 P1		
0.282 (0.86)	0.689 (2.89)				31.013 P5		
3.055 (10.62)	3.691 (12.11)				37.029 F19		
3.265 (10.72)	0.039 (0.13)				35.985 F20		
1.309 (8.36)					37.125 P		
3.190 (10.97)	0.169 (0.55)				37.861 TBM F10/23		TBM F10/23 nail on top of PKNS wall fence.
2.958 (8.05)	0.198 (0.65)				40.117 P25		
18.523	18.935						