

Rajah di muka

[illegible]

CERAPAN MATAHARI BAGI AZIMUT

Penilik Foo Che Yong Hari 20/4/07 Tarikh Bulan Tahun
 Stesen 7 T.R. 9 B.K. Ms. Tiodolait (Jenis) I Bah. Aras Ufuk -a
 Formula: Kosain AZIMUT = $\frac{\text{Kos } P - \text{Sain } \phi \text{ Sain } \alpha}{\text{Kos } \phi \text{ Kos } \alpha}$ Pembetulan Aras $-\frac{3}{8} (\pm R - \pm L)$ tenjen α

Waktu		Ufuk			Gelem-bong		Pugak			Bila waktu jam tangan tidak dalam lingkungan 3 menit daripada waktu piawai Hitung waktu umum.			W.U. $= 12^J + W.T.K. - G. \text{ Bujur} - E$				
J	m	P.Ki	T.R		Ki	Ka											
				26	26	07											
				76	33	77		69	79	55							
				75	58	22		69	39	73							
		P.Ka		255	58	07		295	27	51							
				256	33	17		295	31	70							
Purata ①		T.R															
J	m																
857								25	23	73							
		Purata Ke matahari		76	15	52		1	77								
		Purata Ke T.R.						25	21	59							
J	m	P.Ki	T.R														
				76	32	58		69	18	55							
				75	57	23		69	16	30							
		P.Ka		255	57	05		295	51	19							
				256	32	21		295	56	37							
Purata ②		T.R															
J	m																
								25	47	52							
		Purata Ke matahari		76	17	57		1	71								
		Purata Ke T.R.						25	46	11							
Kordinat Origin U/B		55961			m		Kordinat Origin T/B		21759			m		Purata Bg. Gerid T.R.		270 06 53	
Stesen U/S		2373			m		Stesen T/B		1979			m		Ditilik oleh		20/4/07	
Jumlah/Sel.		58307			m		Jumlah/Sel.		23708			m		Dihitung oleh		MT 20 40 46'	
Jumlah/Sel. $\times 0.03256 \pm$		-0 31 38					Sel. G. Bujur $= \frac{\text{Jum.}}{\text{Sel.}} \times 0.03246 \pm$		12' 50"					Tarikh			
G. Lintang Origin U		3 70 79					Sel. G. Bujur $\times \text{Sain } G. \text{ Lintang} =$										
G. Lintang Stesen U		3 09 11					T (-) / B (+) Tirusan		- 72'								


P.Ki. - Penyilang Kiri
 P.Ka. - Penyilang Kanan

T.R. - Tanda Rujuk
 Sel. - Selisih

W.U. - Waktu Umum
 W.T.K. - Waktu Tempatan Ketara


No. Fail

Rajah di muka



No. Fail

Rajah di muka



Tarikh *Long Stenen.*

Aras

Dibuat untuk

26

Daripada

Ke

WJ

Pandangan Belakang	Pandangan Antara	Pandangan Hadapan	Naik	Turun	Aras Yang Dilaras	Jarak	Catitan
1.390 (19.56)	1.788 (19.88)				38.796		F4
	1.379 (19.51)				38.818		F3
1.699 (15.55)	1.372 (19.50)				36.832		TBM F1155 (alt TBM1)
1.712 (15.61)	1.789 (15.87)				36.839		q
	0.892 (12.83)				37.659		F5
1.796							F7
1.329 (19.36)					38.799		Bm N 0303 AC:38.789m
1.607 (15.23)	1.292 (19.28)						cp
1.731 (18.69)	1.962 (19.80)						q
1.357	1.757 (15.76)				38.605		TBM F1157
	4.51						Di bawah s/b perantara stenen
0.683 (12.28)					38.605		TBM F1157
1.251 (18.13)	1.830 (16.00)						cp
1.268 (19.16)	1.899 (16.06)						cp
	0.879 (15.57)				37.659		F7
3.212	4.158						

*Ilustrasi
Rajut. TBM F1157*

*Y. TBM
empas.*

stena

Tarikh Aras

Dibuat untuk Ke

27

Daripada

Pandangan Belakang	Pandangan Antara	Pandangan Hadapan	Naik	Turun	Aras Yang Dilaras	Jarak	Catitan
1.137 (1373)					37.659		F7
1.464 (1464)		0.858 (282)			37.838		CP F9
1.631 (1535)		1.733 (1569)			37.669		CP F12
	1.510 (1495)				37.730		CP
2.582 (897)		0.945 (314)			38.355		CP
1.600 (1525)		0.650 (213)			40.247		CP
		1.502 (1493)			40.385		TBM F1156 nail on top of sump. (new TBM).
8.914		5.688					
1.502					40.385		TBM F1156
1.266 (1415)		1.280 (1402)					CP
1.077 (1359)		2.275 (1796)					CP
1.383 (1490)		1.962 (1693)					
1.082 (1355)		1.963 (1980)					
2.762 (1906)		1.356 (1495)					
9.032		1.816 (1596)			39.305		TBM F1158 nail on top of division. Airland s/s 5th Run Regak.
1.714 (1562)					39.305		TBM F1158
0.666 (219)		1.132 (1372)					CP
		1.645 (1590)			38.908		TBM F1159 (F2)
2.380		2.717					ESSO Tun Regak. plaster box. divider. Cold Level 38.997 LBO1 M516)

Tarikh Aras

Dibuat untuk

Daripada

Ke

Pandangan Belakang	Pandangan Antara	Pandangan Hadapan	Naik	Turun	Aras Yang Dilaras	Jarak	Catitan
1.385	(4.72)				39305		78m 5/158
1.201	(4.39)	1.715	(4.64)				
1.497	(4.91)	1.750	(5.78)				
1.739	(5.71)	1.743	(4.71)				
5.782		1.867 6.469	(6.13)		35618		78m 5/157