

LEDRIX SDN BHD QUOTATION

70 Jalan S2 C2, Green Technology Park
Seremban 2, Negeri Sembilan (1533672-H)



QUATATION 10

DATE	12/5/2024
QUOTATION	
CUSTOMER ID	

QUOTATION TO

Shah Alam Chinese Methodist Church

DESCRIPTION	PRICE	UNIT	AMOUNT
INDOOR P2.5 MODULE (HIGH REFRESH RATE 3840Hz)	102	305	31,110.00
MAGNET(SET)	1	305	305.00
POWER SUPPLY (200W)	45	52	2,340.00
MODULE RECEIVER 7516	78	21	1,638.00
PROCESSOR v760	650	2	1,300.00
OUTER FRAME AND STRUCTURE	300	17	5,100.00
PSU CABLE	6	28	168.00
MODULE CABLE	25	20	500.00
HDMI MATRIX 4X4	1	750	750.00
NETWORK CABLE (SHORT)	3	20	60.00
LABOUR CHARGE	300	17	5,100.00
			-
			-
			-
			-
			-
			-

Subtotal	48,371.00
Discount%	2,902.26
TOTAL	RM 45,468.74

OTHER COMMENTS

ACTUAL PRESENT SIZE: (3.2*2.4)m² x2
INCLUSIVE FRAME SIZE: 10CM(3.3*2.5)m² x2

6% DISCOUNT FOR CHURCHES, QUOTATION VALIDITY for 15 days

Project description:

Project period: The on-site installation period is 2-3 working days. The above quotation does not include electrical work. If necessary, please inform us in advance.

Warranty time: ① Commitment to 7*24 hours technical team after-sales service; ② One-and half year warranty

Payment method: 30% deposit, 70% balance payment before shipment.

Payment Account: (Affinbank A/c no:101940001631 - LEDRIX SDN.BHD)

Price description: All-inclusive price are LED display panel, inclusive on-site construction costs.

Instructions for use: This product is not waterproof or moisture-proof. Please do not use the LED screen in the above environment.

ITEMS						
SCREEN DETAILS	MODULE	NAME	BRAND	MODAL	UNITx2	DETAIL
RESOLUTION: 1280x960(px) DOT: 1229k SIZE(m): 3.2x2.4(m)	Module: P2.5 [320.0mm x 160.0mm] Pixel: 128 x64 Unit: 10Wx15H	PROCESSOR	NOVASTAR	v960	1	
		CAPTURE CARD	NOVASTAR	v7516	20	
		MODULE	10x15		300	
		POWER SUPPLY (200W)	5x5	200W	50	

